buildable APPROVALS
APPROVED
subject to conditions
FOR CONSTRUCTION
Date: 13/04/2026
0490 102 566

GENERAL NOTES

1. THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL ARCHITECTURAL AND OTHER CONSULTANTS DRAWINGS, THE SPECIFICATIONS AND WITH SUCH OTHER WRITTEN INSTRUCTIONS MAY BE ISSUED DURING THE COURSE OF THE CONTRACT.
2. ANY DISCREPANCY ON THE DRAWINGS OR BETWEEN THE DRAWINGS AND/OR THE SPECIFICATION AND/OR THE SPECIFIED AUSTRALIAN STANDARD SHALL BE REFERRED TO THE ENGINEER AND A WRITTEN INSTRUCTION RECEIVED PRIOR TO PROCEEDING WITH THE WORK. DURING TENDERING THE TENDER SHALL ASSUME THE LARGER/GREATER CRITERIA IN TERMS OF COST IN THE ABSENCE OF OTHER INSTRUCTIONS.
3. ALL MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE CURRENT AUSTRALIAN STANDARDS, INCLUDING ALL AMENDMENTS, NCC AND THE RELEVANT LOCAL AUTHORITIES, EXCEPT WHERE VARIED BY THE PROJECT SPECIFICATION.
4. ALL DIMENSIONS RELEVANT TO SETTING OUT AND OFF-SITE WORK SHALL BE VERIFIED ON SITE BY THE CONTRACTOR BEFORE CONSTRUCTION AND FABRICATION ARE COMMENCED. THE ENGINEERS DRAWINGS ARE NOT TO BE SCALED. NO RESPONSIBILITY WILL BE TAKEN BY THE ENGINEER FOR DIMENSIONS OBTAINED BY SCALING THE DRAWINGS. ALL DIMENSIONS ARE IN mm UNLESS SHOWN OTHERWISE
5. SUBSTITUTIONS MUST BE APPROVED BY THE ENGINEER AND BE INCLUDED IN ANY TENDER.
6. DURING CONSTRUCTION THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE WORKS IN A SAFE MANNER INCLUDING EXCAVATIONS, TEMPORARY SUPPORT AND BRACING IN A STABLE CONDITION.
7. ALWAYS REFER MANUFACTURERS INSTALLATION MANUAL FOR SPECIFIC FIXING REQUIREMENTS AND BEST PRACTICES, INCLUDING USE OF APPROPRIATE BRACKETS AND FIXINGS FOR EXTERNAL USE (e.g. STAINLESS STEEL, HOT DIP GALVANISED OR POWDERCOATED BRACKETS).
8. PROPRIETARY ITEMS (E.G. PURLINS, ROOF/WALL SHEETING, BOLTS ETC.) SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATION
9. THE STRUCTURE SHOWN ON THESE DRAWINGS HAS BEEN DESIGNED FOR THE FOLLOWING DESIGN LOADS:
10. USE A DUSTLESS DRILLING SYSTEM TO ENSURE SLAB HOLES ARE CLEAN. ALTERNATIVELY CLEAN DUST AND DEBRIS FROM HOLE WITH STIFF WIRE OR NYLON BRUSH AND BLOWER IN THE FOLLOWING SEQUENCE: BLOW X2, BRUSH X2, BLOW X2, BRUSH X2, BLOW X2.

LIVE LOADS

FLOORS	1.5kPa / 1.8kN
DECKS/BALCONIES	2.0kPa / 1.8kN
ROOFS	0.25kPa

AS PER AS 1170.1:2002 - STRUCTURAL DESIGN ACTIONS; SECTION 3: IMPOSED ACTIONS

WIND LOADS

WIND RATING OR WIND SPEED TO COMPLY WITH AS4055:2021 OR AS1170.2:2021 AS APPROPRIATE. REFER STA WIND ASSESSMENT REPORT OR APPROVED DOCUMENT BY OTHERS.

PLAN ABBREVIATION KEY

S/S	SINGLE SPAN
C/S	CONTINUOUS SPAN
C/L	CANTILEVER
B/S	BACKSPAN
F/S	FULLY SUPPORTED
(O)	MEMBER OVER
(U)	MEMBER UNDER
GT	GIRDER TRUSS-BY OTHERS
PLY	PLY BRACE
STRAP	STRAP BRACE
AB	METAL OR TIMBER ANGLE BRACE
C/H	CUPHEAD BOLT
BOLT	HEX HEAD BOLT & WASHERS
L	LINTEL-BY OTHERS IF NOT DEFINED
RB	ROOF BEAM-BY OTHERS IF NOT DEFINED
FB	FLOOR BEAM-BY OTHERS IF NOT DEFINED
VT	VOID TRIMMER-BY OTHERS IF NOT DEFINED
LBJ	LOAD BEARING JOIST-BY OTHERS IF NOT DEFINED
FJ	FLOOR JOIST-BY OTHERS IF NOT DEFINED
SC	STEEL COLUMN-BY OTHERS IF NOT DEFINED
TC	TIMBER COLUMN-BY OTHERS IF NOT DEFINED
PTB/C or NBR	POWERTRUSS BRACE /COLUMN or NETBRACE -REFER MANUFACTURER SPECIFICATION AND INSTALLATION DETAILS INCLUDING ANCHORING AT TOP/BOTTOM

STRUCTURAL STEELWORK NOTES

1. ALL MATERIALS, WORKMANSHIP, FABRICATION AND ERECTION SHALL COMPLY WITH THE REQUIREMENTS OF AS4100, AS/NZ4600, AS1554 EXCEPT WHERE VARIED BY CONTRACT DOCUMENTS.
2. ALL STEEL SHALL COMPLY WITH THE FOLLOWING U.N.O. :-
   - WELDED SECTION - GRADE 300 TO AS/NZS 3679.2
   - ROLLED SECTION - GRADE 300 TO AS/NZS 3679.1
   - SHS AND RHS - GRADE 350/GRADE 450 TO AS 1163
   - CHS - GRADE 250/GRADE 350 TO AS 1163
   - FLAT PLATE - GRADE 300 TO AS/NZS 3679.1
   - STANDARD PLATE - GRADE 250 TO AS/NZS 3678
3. UNLESS SHOWN OTHERWISE ON THE DRAWINGS, ALL CONNECTIONS SHALL BE IN ACCORDANCE WITH THE FOLLOWING MINIMUM REQUIREMENTS:
   - A. ALL WELDS SHALL BE 6MM CONTINUOUS FILLET WELDS ALL ROUND OR BUTT WELDS TO BE COMPLETE PENETRATION BUTT WELDS.
   - B. ALL TIMBER TO TIMBER & TIMBER TO STEEL BOLTS TO BE 4.6/s U.N.O.
   - C. ALL STEEL TO STEEL BOLTS TO BE 8.8/s U.N.O.
   - D. ALL GUSSET AND CLEAT PLATES SHALL BE 8mm THICK. UNO.
   - E. ALL CAP PLATES SHALL BE 6mm THICK. UNO.
   - F. ALL BASE PLATES SHALL BE 12mm THICK. UNO.
4. ALL BOLTS SHALL BE HEX HEAD U.N.O. AND AS FOLLOWS :-
   - 4.6/S - COMMERCIAL BOLTS TO AS 1111 AND AS 1112, SNUG TIGHTENED
   - 8.8/S - HIGH STRENGTH STRUCTURAL BOLTS TO AS/NZS 1252, SNUG TIGHTENED ONLY
   - 8.8/TF & 8.8/TB - HIGH STRENGTH STRUCTURAL BOLTS TO AS/NZS 1252, FULLY TENSIONED
5. ALL BOLTS, NUTS AND WASHERS SHALL BE GALVANISED U.N.O. AND COMPLY WITH AS1720 & AS4100.
6. ALL WELDS SHALL BE SP (SPECIAL PURPOSE) IN ACCORDANCE WITH AS1554. ALL BUTT WELDS SHALL BE FULL STRENGTH COMPLETE PENETRATION WELDS. ALL ELECTRODES SHALL BE CLASS E48.
7. IT IS NOT PERMISSIBLE TO SUBSTITUTE DURAGAL SECTIONS FOR GALVANISED SECTIONS WITHOUT WRITTEN APPROVAL FROM STRUCTURAL ENGINEER.
8. THE CONTRACTOR SHALL PROVIDE ALL CLEATS AND DRILL ALL HOLES NECESSARY FOR FIXING STEEL, TIMBER AND OTHER ELEMENTS TO STEEL WHETHER OR NOT DETAILED ON THE STRUCTURAL DRAWINGS.
9. THE FABRICATION AND ERECTION OF THE STRUCTURAL STEELWORK SHALL BE SUPERVISED BY QUALIFIED PERSONNEL EXPERIENCED IN SUCH SUPERVISION TO ENSURE THAT ALL REQUIREMENTS OF THE DESIGN ARE MET. THE CONTRACTOR SHALL PROVIDE TEMPORARY BRACING AND LEAVE IN PLACE UNTIL PERMANENT BRACING ELEMENTS ARE CONSTRUCTED, SUCH TEMPORARY BRACING IS NECESSARY TO STABILISE THE STRUCTURE DURING CONSTRUCTION
10. THE ENDS OF ALL TUBULAR MEMBERS ARE TO BE SEALED WITH NOMINAL THICKNESS PLATES AND 3mm CONTINUOUS FILLET WELDED U.N.O.
11. MASONRY SHALL NOT OVERHANG THE LINTEL WIDTH BY MORE THAN 25mm. WHERE STEEL UNEQUAL ANGLES ARE USED, THE LONGER LEG OF THE ANGLE SHALL BE VERTICAL. ANY GAP BETWEEN THE VERTICAL LEG OF A STEEL ANGLE LINTEL AND THE MASONRY SHALL BE PACKED WITH MORTAR. BRICK LINTEL BEARING LENGTHS ONTO SUPPORTING BRICKWORK EACH END TO BE MINIMUM:
    - 100mm WHERE SUPPORTING <1000mm BRICKWORK OVER
    - 150mm WHERE SUPPORTING <3600mm BRICKWORK OVER
    - 200mm WHERE SUPPORTING <4800mm BRICKWORK OVER

TYPICAL STEEL WASHER SIZES

TIMBER BOLT SIZES IN ACCORDANCE WITH AS1720:2010		STEEL CONNECTIONS IN ACCORDANCE WITH AS1252:2016	
BOLT DIAMETER (mm)	MIN. WASHER SIZE (mm)	BOLT DIAMETER (mm)	WASHER SIZE (mm)
M12 CUPHEAD (C/H)	STANDARD	M12	Ø 25.7 x 3.1
M16 CUPHEAD (C/H)	STANDARD	M16	Ø 32.4 x 3.1
M10 BOLT / COACH SCREW	40 x 40 x 2.5 or Ø 45 x 2.0	M20	Ø 37.4 x 3.1
M12 BOLT / COACH SCREW	50 x 50 x 3.0 or Ø 55 x 3.0	M24	Ø 48.4 x 3.1
M16 BOLT / COACH SCREW	57 x 57 x 4.0 or Ø 65 x 4.0		

TYPICAL HOT ROLLED STEEL SECTION SIZES

SECTION	kg/m	DEPTH	WIDTH	SECTION	kg/m	DEPTH	WIDTH	SECTION	kg/m	DEPTH	WIDTH
200UC	46.2	203	203	250UB	25.7	248	124	150PFC	17.7	150	75
	52.2	206	204		31.4	252	146	180PFC	20.9	180	75
	59.5	210	205		37.3	256	146	200PFC	22.9	200	75
250UC	72.9	254	254	310UB	32.0	298	149	230PFC	25.1	230	75
	89.5	260	256		40.4	304	165	250PFC	35.5	250	90
310UC	96.8	308	305		46.2	307	166	300PFC	40.1	300	90
	118	315	307	360UB	44.7	352	171	380PFC	55.2	380	100
	137	321	309		50.7	356	171				
	158	327	311		56.7	359	172				

PROTECTIVE COATINGS FOR STEELWORK

ENVIRONMENT	LINTELS IN MASONRY	LOCATION	MINIMUM PROTECTIVE COATING — GENERAL STRUCTURAL STEEL MEMBERS	
MEDIUM MORE THAN 1km FROM BREAKING SURF OR MORE THAN 100m FROM SALT WATER NOT SUBJECT TO BREAKING SURF OR NON-HEAVY INDUSTRIAL AREA	R3	INTERNAL	OPTION 1	ZINC RICH PRIMER (75µm) + 2 COATS OF ACRYLIC PAINT (40µm)
			OPTION 2	1 PACK ZINC PHOSPHATE EPOXY PRIMER (100µm)
	R3	EXTERNAL	OPTION 1	HOT DIP GALVANISE 100g/m²min. + 2 PACK ZINC PHOSPHATE EPOXY PRIMER (75µm) + HIGH-BUILD EPOXY (150µm)
			OPTION 2	HOT DIP GALVANISE 300g/m²min.
HIGH WITHIN 1km FROM BREAKING SURF OR WITHIN 100m OF SALT WATER NOT SUBJECT TO BREAKING SURF OR HEAVY INDUSTRIAL AREA	R4	INTERNAL	OPTION 1	1 COAT HIGH-BUILD ALKYD PRIMER (75µm) + HIGH-BUILD ALKYD GLOSS (40µm)
			OPTION 2	1 PACK ZINC PHOSPHATE EPOXY PRIMER (100µm) + 1 COAT OF 2 PACK ACRYLIC
	R4	EXTERNAL	OPTION 1	ZINC RICH PRIMER (75µm) + 1 COAT EPOXY MIO (75µm) + 1 COAT EPOXY MIO (175µm)
			OPTION 2	INLINE GALVANISE 100g/m²min. + 2 PACK ZINC PHOSPHATE EPOXY PRIMER (75µm) + 1 COAT EPOXY MIO (175µm)
			OPTION 3	HOT DIP GALVANISE 600g/m²min.
VERY HIGH WITHIN 50m OF BREAKING SURF	R5	EXTERNAL ONLY	OPTION 1	HOT DIP GALVANISE 600g/m²min. + 2 PACK ZINC PHOSPHATE EPOXY PRIMER (75µm) + 1 COAT EPOXY MIO (175µm)

NOTE: REFER TO AS2312.1 FOR ALTERNATIVE PROTECTIVE COATINGS (MIN. +25 YEARS)

NOTE:

1. THE OUTER LEAF AND CAVITY OF AN EXTERNAL MASONRY WALL OF A BUILDING, INCLUDING WALLS UNDER OPEN CARPORTS ARE CONSIDERED TO BE EXTERNAL ENVIRONMENTS. A PART OF AN INTERNAL LEAF OF AN EXTERNAL MASONRY WALL WHICH IS LOCATED IN THE ROOF SPACE IS CONSIDERED AN INTERNAL ENVIRONMENT.
2. WHERE A PAINT FINISH IS APPLIED, THE SURFACE OF THE STEELWORK MUST BE CLEANED TO REMOVE ANY RUST IMMEDIATELY PRIOR TO PAINTING. FOR SEVER EXPOSURE THE SURFACE MUST BE CLEANED TO AS1627 CLASS 2.5 PRIOR TO PAINING.
3. ALL ZINC COATINGS (INCLUDING ORGANIC ZINC) REQUIRE A BARRIER COAT TO STOP CONVENTIONAL DOMESTIC ENAMELS FROM PEELING.
4. WHERE A PAINT SYSTEM IS APPLIED TO METALLIC COATED STEEL SURFCES, APPROPRIATE SURFACE PREPARATION MUST BE CARRIED OUT IN ACCORDANCE WITH AS/NZS 2312.
5. REFER TO THE PAINT MANUFACTURER WHERE DECORATIVE FINISHES ARE REQUIRED ON TOP OF THE MINIMUM COATING SPECIFIED IN THE TABLE FOR PROTECTION OF THE STEEL AGAINST CORROSION.
6. WHERE METALLIC COATED STEEL COMPONENTS ARE FABRICATED BY WELDING, THE WELD AND ADJOINING AREAS MUST BET TOUCHED UP WITH A ZINC RICH PAINT OR EQUIVALENT COATING SYSTEM IN ACCORDANCE WITH AS/NZS 2312 AND AS/NZS 4680.

TIMBER NOTES

1. ALL WORKMANSHIP, MATERIALS, TIMBER CONNECTIONS SHALL BE IN ACCORDANCE WITH AS 1720, AS 1684 UNLESS DESIGNED OR DETAILED OTHERWISE.
2. ALL PROPRIETARY CONNECTORS ARE TO BE INSTALLED IN ACCORDANCE WITH MANUFACTURERS DETAILS.
3. TIMBER BEAMS/LINTELS WHERE DESIGNED BY STA AS PER DEFLECTION CRITERIA IN AS1720.3.
4. ALL TIMBER TO BE MIN. JOINT GROUP JD5 U.N.O.
5. BLOCKING BETWEEN JOISTS/RAFTERS/PURLINS AT MAX 1800c/c AND OVER SUPPORTS U.N.O. FIXED AS PER MANUFACTURERS SPECIFICATIONS.
6. BINDERS WHERE REQUIRED TO BE SPECIFIED BY TRUSS SUPPLIER U.N.O.
7. BOTTOM CHORD BRACING WHICH IS STRUCTURALLY ADEQUATE TO TRANSFER THE WIND LOADS FROM THE ROOF TRUSSES TO THE NOMINATED BRACING WALLS IS TO BE INSTALLED IF PLASTERBOARD CEILING NOT PRESENT. TO BE SPECIFIED BY TRUSS SUPPLIER U.N.O.
10. ALL EXTERNAL AND EXPOSED ABOVE GROUND FRAMING TIMBER TO BE MIN. H3 TREATED U.N.O. PROVIDE MALTHOID STRIPS OR EQUIV OVER LVLs AND TREAT CUT ENDS FOR DURABILITY. ALWAYS REFER MANUFACTURERS SPECIFICATIONS FOR INSTALLATION REQUIREMENTS.
11. ALL FLOOR BEARER/JOISTS MUST BE SUPPORTED BY TIMBER FLOOR BEAM, LINTEL OR LOAD BEARING WALL, NOT EXTERNAL BRICKWORK.

– REPORT NAME	256865 STA JOB #	
Arcadia Homes QLD CLIENT	CLIENT REFERENCE	CLIENT JOB #
Lot 16 3 POWERS COURT EUMUNDI QLD 4562 ADDRESS	SP 325615 RP / SP NUMBER	
SUNSHINE COAST REGIONAL COUNCIL LOCAL AUTHORITY		

ISSUE	ISSUE DESCRIPTION	DATE
0	CONSTRUCTION ISSUE	15/09/25
1	AMENDMENT = UPDATED FLOOR PLAN	28/01/26
-	-	-
-	-	-

SCALE NTS U.N.O.

WIND LOADING **55.30m/s**

Smart, practical engineering solutions for residential construction
Powered by STA.

STA CONSULTING ENGINEERS

COPYRIGHT © 2021
ISO 9001:2015 Certified

DRG NO. S01 | DRG TOTAL -

A3 SHEET SIZE

buildable APPROVALS
APPROVED
subject to conditions
No. 20261196
Date: 13/04/2026
Miranda Dowling A15335397
Qualified Level 3 Assessor Limited Licence
0490 402 566

TABLE 9.4 A

THE FOLLOWING CALCULATIONS ARE BASED ON AND TAKEN FROM:AS 1684:2021 - RESIDENTIAL TIMBER-FRAMED CONSTRUCTION.


IF TIE DOWN IS SHOWN ON PLAN, DESIGN MAY DIFFER FROM BELOW TABLE WHERE APPLICABLE.

TIE-DOWN SCHEDULE	≤58.0 m/s	SHEET		ULW:	6000	
				TRUSS SPACING:	900	NOMINATED FRAME TIE-DOWN IS TO BE INSTALLED TO ALL LEVELS OF STRUCTURE.
TIE-DOWN MEMBER	SPECIFIC ULW	SPACING /SPAN	UPLIFT FORCE (kN)	FIGURE No.	CAPACITY (kn)	DESCRIPTION/TYPE OF FIXING
BATTEN TO TRUSS OR RAFTER (GENERAL & EDGES)	900	900	3.4	TABLE 9.25d	3.6 (JD5)	1/14G×75 TYPE 17 BATTEN SCREW
TRUSS/RAFTER TO TOP PLATE	6000	900	10.3	TABLE 9.21e	13.0	1/30×0.8mm G.I STRAP LOOPED UNDER TOP PLATE/BEAM, 4/2.8ø(JD4) OR 5/2.8ø(JD5) NAILS PER END INTO SIDE OF MEMBER
TOP PLATE TO FLOOR FRAME OR SLAB	6000	450	5.2	TABLE 9.19d	6.9 (JD5)	30×0.8mm G.I STRAP LOOPED OVER/UNDER TOP/BOTTOM PLATE, 6/2.8ø NAILS PER END TO STUD & M12 BOLT TO SLAB REFER STRAP TIE DOWN DETAILS FOR FIXING TO FLOOR SYSTEM UNDER
	6000	900	10.3	TABLE 9.19g	20.0 (JD4)	M12 ANCHOR ROD AT SPACING INDICATED IN THIS TABLE AND AT ENDS OF WALLS U.N.O.
TOP PLATE TO FLOOR FRAME OR SLAB (REDUCED ULW/HIP ENDS)	2400	900	4.1	TABLE 9.19d	6.9 (JD5)	30×0.8mm G.I STRAP LOOPED OVER/UNDER TOP/BOTTOM PLATE, 6/2.8ø NAILS PER END TO STUD & M12 BOLT TO SLAB REFER STRAP TIE DOWN DETAILS FOR FIXING TO FLOOR SYSTEM UNDER
BEAMS/LINTELS TO FLOOR FRAME OR SLAB	6000	1500	13.8	TABLE 9.20b	14.0 (JD5)	2/30×0.8mm G.I STRAP LOOPED OVER/UNDER TOP/BOTTOM PLATE, 6/2.8ø NAILS PER END TO 2/STUDS & M12 BOLT TO SLAB, REFER STRAP TIE DOWN DETAILS FOR FIXING TO FLOOR SYSTEM UNDER
	6000	2500	19.5	TABLE 9.20c	20.0 (JD4)	M12 ANCHOR ROD, TOP PLATE TO SLAB/FLOOR FRAME & M12 BOLT TOP PLATE TO LINTEL WITHIN 100mm OF TRUSS/RAFTER
	6000	5100	34.4	TABLE 9.20d	35.0 (JD4)	M16 ANCHOR ROD, TOP PLATE TO SLAB/FLOOR FRAME & TOP PLATE TO LINTEL WITHIN 100mm OF TRUSS/RAFTER
BEAMS/LINTELS TO FLOOR FRAME OR SLAB (REDUCED ULW/HIP ENDS)	2400	2100	6.9	TABLE 9.20b	6.9 (JD5)	30×0.8mm G.I STRAP LOOPED OVER/UNDER TOP/BOTTOM PLATE, 6/2.8ø NAILS PER END TO STUD & M12 BOLT TO SLAB REFER STRAP TIE DOWN DETAILS FOR FIXING TO FLOOR SYSTEM UNDER
	2400	5200	14.0	TABLE 9.20b	14.0 (JD5)	2/30×0.8mm G.I STRAP LOOPED OVER/UNDER TOP/BOTTOM PLATE, 6/2.8ø NAILS PER END TO 2/STUDS & M12 BOLT TO SLAB, REFER STRAP TIE DOWN DETAILS FOR FIXING TO FLOOR SYSTEM UNDER
	2400	6000	15.8	TABLE 9.20c	20.0 (JD4)	M12 ANCHOR ROD, TOP PLATE TO SLAB/FLOOR FRAME & M12 BOLT TOP PLATE TO LINTEL WITHIN 100mm OF TRUSS/RAFTER


NOTE:
1. TIE DOWN MEMBERS NOT IN THIS TABLE REFER NOMINAL FIXINGS TABLES
2. THE ABOVE TABLES HAVE BEEN DESIGNED FOR TIMBER WITH A MINIMUM JOINT GROUP OF JD5 U.N.O., CONTACT STA IF JOINT GROUP OF TIMBER IN USE DIFFERS TO WHAT IS SHOWN IN TABLE.
3. AS PER 1684; THE TOP PLATE SHALL BE FIXED OR TIED TO THE LINTEL WITHIN 100mm OF EACH RAFTER/TRUSS, OR THE RAFTER/TRUSS FIXED DIRECTLY TO THE LINTEL WITH A FIXING OF EQUIVALENT TIE DOWN STRENGTH TO THAT REQUIRED FOR THE RAFTER/TRUSS.
4. FRAME, TRUSS AND ROOF BATTEN TIE DOWN MAY BE SUBSTITUTED WITH EQUIVALENT STRENGTH ALTERNATIVE PROVIDED BY TRUSS MANUFACTURER IF ACCOMPANIED BY A RELEVANT DESIGN CERTIFICATE, GIRDER TRUSS TIE DOWN BY MANUFACTURER.
5. TOP PLATE & BEAM/LINTEL TIE DOWN METHODS IN TABLE ABOVE HAVE BEEN DESIGNED ASSUMING MINIMUM 2/MGP12 (JD4) TOP/RIBBON PLATES. CONTACT STA IF TIMBER GRADE USED DIFFERS.

TABLE 9.4B - NOMINAL FIXINGS FOR TIMBER MEMBERS

FLOOR FRAMING	
BEARER TO TIMBER STUMP/POST	4/75 x 3.33mm OR 5/75 x 3.05mm MACHINE-DRIVEN NAILS PLUS 1/30 x 0.8mm G.I. STRAP OVER BEARER AND FIXED BOTH ENDS TO STUMP WITH 4/2.8mm ø EACH END; OR 1/M10 BOLT THROUGH BEARER HALVED TO STUMP; OR 1/M12 CRANKED BOLT FIXED VERTICALLY THROUGH BEARER AND BOLTED TO STUMP PLUS 4/75 x 3.33mm 5/75 x 3.05mm MACHINE-DRIVEN NAILS
BEARER TO MASONRY COLUMN/WALL/PIER (EXCLUDING MASONRY VENEER CONSTRUCTION)	1/M10 BOLT OR 1/50 x 4mm MILD STEEL BAR FIXED TO BEARER WITH M10 BOLT AND CAST INTO MASONRY (TO FOOTING)
BEARER TO CONCRETE STUMP/POST	1/6mm ø ROD CAST INTO STUMP, VERTICALLY THROUGH BEARER AND BENT OVER
BEARERS TO STEEL POST	1/M10 COACH SCREW OR BOLT
FLOOR JOIST TO BEARER	2/75 x 3.05 mm ø NAILS
WALL FRAMING	
PLATES TO STUDS	PLATES UP TO 38mm THICK - 2/75mm NAILS THROUGH PLATE PLATES 38 TO 50mm THICK - 2/90mm NAILS THROUGH PLATE; OR 2/75mm NAILS SKEWED THROUGH STUD INTO PLATE.
NOGGINGS TO STUDS	2/75mm NAIL SKEWED OR THROUGH NAILED
BOTTOM PLATES TO JOISTS	PLATES UP TO 38mm THICK 2/75mm NAILS AT MAX. 600mm crs. PLATES 38 TO 50mm THICK - 2/90mm NAILS AT MAX. 600mm crs.
BOTTOM PLATES TO CONCRETE SLAB	ONE 75mm MASONRY NAIL (HAND DRIVEN AT SLAB EDGE), SCREW OR BOLT AT NOT MORE THAN 1200mm crs.
MULTIPLE STUDS	1/75mm NAIL AT 600 crs. MAX.
POSTS TO BEARERS OR JOISTS	1/M12 OR 2/M10 BOLTS (UNLESS OTHERWISE SPECIFIED)
ROOF FRAMING	
ROOF TRUSSES TO TOP PLATES & BATTENS TO ROOF TRUSSES	REFER TO TABLE 9.4a
RAFTER TO TOP PLATE - NON-COUPLED	2/75mm SKEW NAILS
VERANDAH BEAMS/ROOF BEAMS TO POST	1/M12 OR 2/M10 BOLTS (UNLESS OTHERWISE SPECIFIED FOR TIE-DOWN)



TYPICAL TIE DOWN ROD CONTINUATION DETAIL
(N3+, CYCLONIC AND GREATER THAN 40m/s U.N.O.)



TYPICAL TIE DOWN ROD CONTINUATION DETAIL
(N1, N2 AND LESSER OR EQUAL TO 40m/s U.N.O.)

- REPORT NAME		256865 STA JOB #	ISSUE	ISSUE DESCRIPTION	DATE
Arcadia Homes QLD CLIENT	CLIENT REFERENCE	CLIENT JOB #	0	CONSTRUCTION ISSUE	15/09/25
Lot 16 3 POWERS COURT EUMUNDI QLD 4562 ADDRESS		SP 325615 RP / SP NUMBER	1	AMENDMENT = UPDATED FLOOR PLAN	28/01/26
			-	-	-
SUNSHINE COAST REGIONAL COUNCIL LOCAL AUTHORITY			-	-	-

SCALE NTS U.N.O.

WIND LOADING **55.30m/s**

Smart, practical engineering solutions for residential construction
Powered by STA.


COPYRIGHT © 2021
ISO 9001:2015 Certified

STA CONSULTING ENGINEERS

DRG NO. S02 | DRG TOTAL -

A3 SHEET SIZE


buildable APPROVALS
APPROVED
subject to conditions
No. 20261196
Date: 13/04/2026
Miranda Dowling A153A5390
QBCC Level 3 - Accredited Certifier
0490 102 566



ROOF BEAM FIXING DETAIL (PLAN) ROOF BEAM FIXING DETAIL (SECTION)


TYPICAL TIMBER ROOF BEAMS TO CORNER TIMBER COLUMN DETAIL

SCALE N.T.S.




TYPICAL TIMBER COLUMN SUPPORTING ROOF LOAD TO FLOOR DETAIL

NOT TO SCALE




ROOF BEAM FIXING DETAIL (SECTION)




ROOF BEAM FIXING DETAIL (PLAN)

TYPICAL TIMBER ROOF BEAM TO CORNER SHS COLUMN DETAILS


SCALE NTS






TYPICAL ROOF BEAM TIE DOWN DETAILS

NOT TO SCALE



ROOF BEAM FIXING DETAIL (SECTION)



ROOF BEAM FIXING DETAIL (PLAN)

TYPICAL TIMBER ROOF BEAM TO CORNER SHS COLUMN DETAILS

SCALE NTS

NOTE:

1. d= BOLT DIAMETER AND REFERS TO MINIMUM DISTANCES TO EDGE OF MEMBERS AND BETWEEN FIXINGS.
2. REFER SPECIFIC SECTION/DETAIL IN THIS DRAWING SET IF FIXING IN ROOF BEAM TO COLUMN TIE DOWN TABLE IS LISTED AS N/A.
3. THE BELOW TABLE HAS BEEN DESIGNED FOR TIMBER WITH A MINIMUM JOINT GROUP OF JD4 U.N.O., CONTACT STA IF JOINT GROUP OF TIMBER IN USE DIFFERS TO WHAT IS SHOWN IN TABLE.

ROOF BEAM TO TIMBER/STEEL COLUMN TIE DOWN TABLE, ≤58m/s SHEET ROOF (JD4)

BEAM TIE DOWN SPACING	<2000					<3000					<4000					<5000				
CONNECTION TYPE	2000 ULW	3000 ULW	4500 ULW	6000 ULW	7500 ULW	2000 ULW	3000 ULW	4500 ULW	6000 ULW	7500 ULW	2000 ULW	3000 ULW	4500 ULW	6000 ULW	7500 ULW	2000 ULW	3000 ULW	4500 ULW	6000 ULW	7500 ULW
STEEL	2/M12	2/M12	2/M16	2/M16	N/A	2/M12	2/M16	2/M16	N/A	N/A	2/M12	2/M16	N/A	N/A	N/A	2/M16	N/A	N/A	N/A	N/A
TIMBER 1	2/M12	2/M12	2/M16	2/M16	N/A	2/M12	2/M16	2/M16	N/A	N/A	2/M12	2/M16	N/A	N/A	N/A	2/M16	N/A	N/A	N/A	N/A
TIMBER 2	2/M12	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
STEEL - CUPHEAD	2/M12	2/M16	N/A	N/A	N/A	2/M16	N/A	N/A	N/A	N/A	2/M16	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
TIMBER 1 - CUPHEAD	2/M12	2/M16	N/A	N/A	N/A	2/M16	N/A	N/A	N/A	N/A	2/M16	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
TIMBER 2 - CUPHEAD	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
SCREWS	4	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

- REPORT NAME		256865 STA JOB #	ISSUE	ISSUE DESCRIPTION	DATE
Arcadia Homes QLD CLIENT	CLIENT REFERENCE	CLIENT JOB #	0	CONSTRUCTION ISSUE	15/09/25
Lot 16 3 POWERS COURT EUMUNDI QLD 4562 ADDRESS		SP 325615 RP / SP NUMBER	1	AMENDMENT = UPDATED FLOOR PLAN	28/01/26
			-	-	-
SUNSHINE COAST REGIONAL COUNCIL LOCAL AUTHORITY			-	-	-

SCALE NTS U.N.O. WIND LOADING 55.30m/s

Smart, practical engineering solutions for residential construction
Powered by STA.


STA CONSULTING ENGINEERS

COPYRIGHT © 2021
ISO 9001:2015 Certified


DRG NO. S03 | DRG TOTAL -

A3 SHEET SIZE


buildable APPROVALS
APPROVED
subject to conditions
No. 2026/1006
Date: 13/04/2026
Miranda Dowling A15335397
QBCC Level 3 - Accredited Certifier
0490 102 566



TYPICAL FLOOR & ROOF BEAM TO SHS COLUMN DETAIL
NOT TO SCALE




EXTERNAL WALL ON SLAB EDGE




INTERNAL WALL ON INTERNAL SLAB / WAFFLE POD


ROOF/FLOOR BEAM ROD TIE DOWN TO SLAB DETAILS
NOT TO SCALE



UNEQUAL ANGLE OPTION
SINGLE/DOUBLE ANGLE AS PER TABLE




'L' BEARER / LOAD BEARING JOIST INTERSECTION




'T' CORNER BEARER / LOAD BEARING JOIST INTERSECTION

TYPICAL INLINE BEARER / LOAD BEARING JOIST INTERSECTION DETAILS
NOT TO SCALE




STRAP OPTION
SINGLE/DOUBLE STRAP AS PER TABLE




HD BRACKET OPTION
SINGLE/DOUBLE BRACKET AS PER TABLE

ROOF/FLOOR BEAM TIE DOWN DETAILS
SCALE N.T.S.



TYPICAL ABUTTING TIMBER MEMBERS OVER SHS DETAIL
NOT TO SCALE



TYPICAL NOTCHED TIMBER MEMBER OVER SHS DETAILS
NOT TO SCALE

ROOF/FLOOR BEAM TIE DOWN TABLE, ≤58m/s SHEET ROOF (JD4) — Y = APPLICABLE METHOD, NA = NOT APPLICABLE

	BEAM TIE DOWN SPACING	<2000					<3000					<4000					<5000				
	CONNECTION TYPE	2000 ULW	3000 ULW	4500 ULW	6000 ULW	7500 ULW	2000 ULW	3000 ULW	4500 ULW	6000 ULW	7500 ULW	2000 ULW	3000 ULW	4500 ULW	6000 ULW	7500 ULW	2000 ULW	3000 ULW	4500 ULW	6000 ULW	7500 ULW
ROOF	SINGLE TIEDOWN	Y	Y	NA	NA	NA	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
ROOF	DOUBLE TIEDOWN	Y	Y	Y	Y	NA	Y	Y	Y	NA	NA	Y	Y	NA	NA	NA	Y	NA	NA	NA	NA
FLOOR	SINGLE TIEDOWN	Y	Y	NA	NA	NA	Y	NA	NA	NA	NA	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA
FLOOR	DOUBLE TIEDOWN	Y	Y	Y	Y	Y	Y	Y	Y	NA	NA	Y	Y	NA	NA	NA	Y	Y	NA	NA	NA
FLOOR	SHS - M12 CUPHEADS	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
FLOOR	SHS - 2/M12	Y	Y	Y	Y	NA	Y	Y	Y	NA	NA	Y	Y	NA	NA	NA	Y	NA	NA	NA	NA
FLOOR	SHS - 2/M16	Y	Y	Y	Y	Y	Y	Y	Y	Y	NA	Y	Y	Y	NA	NA	Y	Y	NA	NA	NA
FLOOR	SHS - 4/M12	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	NA	Y	Y	Y	NA	NA
FLOOR	SHS - 4/M16	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y

- REPORT NAME		256865 STA JOB #	ISSUE	ISSUE DESCRIPTION	DATE
Arcadia Homes QLD CLIENT	CLIENT REFERENCE	CLIENT JOB #	0	CONSTRUCTION ISSUE	15/09/25
			1	AMENDMENT = UPDATED FLOOR PLAN	28/01/26
Lot 16 3 POWERS COURT EUMUNDI QLD 4562 ADDRESS		SP 325615 RP / SP NUMBER	-	-	-
SUNSHINE COAST REGIONAL COUNCIL LOCAL AUTHORITY			-	-	-

SCALE NTS U.N.O.
WIND LOADING 55.30m/s

Smart, practical engineering solutions for residential construction
Powered by STA.

STA CONSULTING ENGINEERS

COPYRIGHT © 2021
ISO 9001:2015 Certified


DRG NO. S04 | DRG TOTAL -

A3 SHEET SIZE


bundable APPROVALS
APPROVED
subject to conditions
ASSESSED FOR
RULE OF DESIGN
Miranda Bowring A15855397
QBCC Licence Type Qualifier
0180201566

GENERAL NOTES:

1. SUITABILITY OF TIE DOWN DETAILS TO BE ASSESSED AND SPECIFIED ON A SITE SPECIFIC BASIS BY STA CONSULTING ENGINEERS ACCOMPANIED BY RELEVANT DESIGN CERTIFICATION.
2. STRAP TIE DOWN ONLY TO BE USED WHERE SHOWN ON PLAN (WHERE APPLICABLE) OR IF NOTED IN TIE DOWN TABLE.
3. REFER TO BRACING DETAILS SHEET DRAWING S05 FOR SPECIFIC BRACING TIE DOWN REQUIREMENTS. STRAP DETAILS SHOWN ON THIS SHEET ARE FOR FRAME TIE DOWN ONLY BUT MAY BE USED IF BRACING TIE DOWN REQUIREMENTS ARE MET, ADDITIONAL SCREWS OR BOLTS/RODS MAY BE REQUIRED.




SINGLE LOOPED STRAP 6.9 kN (JD5)




DOUBLE LOOPED STRAP 14.0 kN (JD5)

TOP PLATE CONNECTIONS
SCALE NTS




SINGLE STRAP 6.5 kN (JD5)




DOUBLE STRAP 13.0 kN (JD5)

BOTTOM PLATE CONNECTIONS
LINTEL/FRAME UNDER - OPTION 1
SCALE NTS




SINGLE LOOPED STRAP 6.9 kN (JD5)




DOUBLE LOOPED STRAP 14.0 kN (JD5)

BOTTOM PLATE CONNECTIONS
OVER BEAM - OPTION 1
SCALE NTS




SINGLE STRAP 6.5 kN (JD5)



DOUBLE STRAP 13.0 kN (JD5)

BOTTOM PLATE CONNECTIONS
OVER BEAM - OPTION 2
SCALE NTS



BOTTOM PLATE CONNECTION
TO SLAB
SCALE NTS

REPORT NAME: –		STA JOB #: 256865	ISSUE	ISSUE DESCRIPTION	DATE
CLIENT: Arcadia Homes QLD	CLIENT REFERENCE:	CLIENT JOB #:	0	CONSTRUCTION ISSUE	15/09/25
			1	AMENDMENT = UPDATED FLOOR PLAN	28/01/26
ADDRESS: Lot 16 3 POWERS COURT EUMUNDI QLD 4562		RP / SP NUMBER: SP 325615	–	–	–
LOCAL AUTHORITY: SUNSHINE COAST REGIONAL COUNCIL			–	–	–

SCALE: NTS U.N.O.

WIND LOADING **55.30m/s**

Smart, practical engineering solutions for residential construction
Powered by STA.

COPYRIGHT © 2021
ISO 9001:2015 Certified

STA CONSULTING ENGINEERS


DRG NO. S05 | DRG TOTAL -

A3 SHEET SIZE

buildable
APPROVED
subject to conditions
No. 20261196
Date: 13/04/2026
Miranda Dowling A15335397
QBCC Level 3 - Accredited Certifier
Lic no. 03566


BRACING & TIE DOWN NOTES:

1. PLYWOOD SHALL BE NAILED TO FRAME USING 30mm x 2.8mm Φ FLATHEAD NAILS OR EQUIVALENT. NAILS SHALL BE LOCATED MIN. 15mm FROM TOP/BOTTOM EDGES AND 10mm FROM VERT EDGES.
2. M12 RODS/BOLTS TO BE PLACED AT EITHER END OF PLY BRACING PANELS & ALSO AT MAX 1200c/c AS PER BRACING TYPES PLY1/2. NOMINAL/BATTEN SCREW FIXING FOR AB/STRAP BRACES/PLY3.
3. SHEATHED PANELS SHALL BE CONNECTED TO SUBFLOOR.
4. WHERE PLY BRACING IS FIXED TO BOTH SIDES OF A WALL, THE DEPTH OF BOTTOM PLATE SHALL BE A MINIMUM OF 45mm AND TIE DOWN IS TO BE DOUBLED AT ALL LOCATIONS
5. ALWAYS REFER MANUFACTURERS INSTALLATION REQUIREMENTS AND GUIDELINES FOR PROPRIETARY PRODUCTS, DETAILS INCLUDED IN THESE DRAWINGS ARE INDICATIVE AND STA IS TO BE CONTACTED IF DETAILS DIFFER AT TIME OF CONSTRUCTION.
6. NON-CRACKED CONCRETE SLABS HAVE BEEN ASSUMED FOR DESIGN OF CHEMICAL ANCHOR FIXINGS IN THIS DRAWING. STA IS TO BE CONTACTED IF CONCRETE SLAB HAS BEEN DESIGNED AS CRACKED.




M12 ROD/BOLT (20kN): CHEMSET 502 PLUS, 120 EMBEDMENT
M16 ROD/BOLT (35kN) CHEMSET 502 PLUS, 210 EMBEDMENT


CHEMICAL ANCHORING SUBSTITUTIONS TO MANUFACTURERS SPECIFICATION, IF IN DOUBT CONTACT STA CONSULTING.



NOTE: THIS DETAIL MAY ONLY BE APPLIED WHERE SPECIFIED BRACING TYPE REQUIRES BOLTS ONLY OR IF TIE DOWN IS SPECIFICALLY SHOWN ON PLAN. WHERE CHEMSET RODS ARE REQUIRED OR IF SHOWN ON PLAN, SLAB MUST BE THICKENED ACCORDINGLY TO ACCOMMODATE ADEQUATE EMBEDMENT DEPTH AND SUBSTRATE THICKNESS TO PRODUCT MANUFACTURER'S DETAILS.




45mm BOTTOM PLATE BOLT TIE DOWN



35mm BOTTOM PLATE BOLT/ROD TIE DOWN

TYPICAL TIE DOWN SLAB EDGE FIXING DETAIL
NOT TO SCALE




MINIMUM PLYWOOD THICKNESS (mm)			POSITION	LENGTH
			BRACING CAPACITY (kN/m)	
STRESS GRADE	STUD SPACING (mm)		INTERNAL	≥600 - <900
	450	600	4.0 (JD5)	
			EXTERNAL	≥450 - <600
F8	7	9	4.0 (JD5)	
F11	6	7	EXTERNAL	≥600 - <900
F14	4	6	5.6 (JD5)	
F27	4	4.5		

PLYWOOD BRACING (PLY-1)

PER TABLE 8.18 OF AS 1684.2/3: 2021
TYPE (H) METHOD A


(PLY-1) TYPICAL PLY BRACING DETAIL (LENGTH>450mm)
NOT TO SCALE



PER TABLE 8.18 OF AS 1684.2/3: 2021
TYPE (B & D)


(STRAP) G.I. METAL STRAP BRACING DETAIL (1.5 / 3.0 kN/m)
NOT TO SCALE

INTERNAL/WAFFLE POD FIXING DETAIL
NOT TO SCALE




PER TABLE 8.18 OF AS 1684.2/3: 2021
TYPE (C)

(AB) METAL ANGLE BRACING DETAIL (1.5kN/m)
NOT TO SCALE



14g T17 SCREW GROUPING DETAIL
NOT TO SCALE




MINIMUM PLYWOOD THICKNESS (mm)			BRACING CAPACITY
STRESS GRADE	STUD SPACING (mm)		5.2 kN/m (JD5)
	450	600	
F8	7	9	
F11	6	7	
F14	4	6	
F27	4	4.5	

PLYWOOD BRACING (PLY-2)

PER TABLE 8.18 OF AS 1684.2/3: 2021
TYPE (H) METHOD B

(PLY-2) TYPICAL PLY BRACING DETAIL (LENGTH>900mm)
NOT TO SCALE



PER TABLE 8.18 OF AS 1684.2/3: 2021
TYPE (G)

(PLY-3) TYPICAL PLY BRACING DETAIL (LENGTH>900mm)
NOT TO SCALE

MINIMUM PLYWOOD THICKNESS (mm)			BRACING CAPACITY
STRESS GRADE	STUD SPACING (mm)		3.0 kN/M (JD5)
	450	600	
NO NOGGING (EXCEPT HORIZONTAL BUTT JOINTS)			
F8	7	9	
F11	4.5	7	
F14	4	6	
F27	3	4.5	
ONE ROW OF NOGGING			
F8	7	7	
F11	4.5	4.5	
F14	4	4	
F27	3	3	

PLYWOOD BRACING (PLY-3)

- REPORT NAME		256865 STA JOB #	ISSUE	ISSUE DESCRIPTION	DATE
Arcadia Homes QLD CLIENT	CLIENT REFERENCE	CLIENT JOB #	0	CONSTRUCTION ISSUE	15/09/25
Lot 16 3 POWERS COURT EUMUNDI QLD 4562 ADDRESS		SP 325615 RP / SP NUMBER	1	AMENDMENT = UPDATED FLOOR PLAN	28/01/26
			-	-	-
SUNSHINE COAST REGIONAL COUNCIL LOCAL AUTHORITY			-	-	-

SCALE NTS U.N.O.
WIND LOADING 55.30m/s

Smart, practical engineering solutions for residential construction
Powered by STA.


STA CONSULTING ENGINEERS

COPYRIGHT © 2021
ISO 9001:2015 Certified

DRG NO. S06 | DRG TOTAL -


A3 SHEET SIZE

buildable
APPROVED
subject to conditions
No. 20261196
Date: 13/04/2026
Miranda Dowling A15335397
QBCC Level 3 - Accredited Certifier
0440 102 566




SCREWS	JD5
2	4.9
3	7.4

JOIST/RAFTER PARALLEL (DIRECT FIXING) TO BRACING WALL




SCREWS	JD5
2	4.9
3	7.4

TRUSS/RAFTER PARALLEL TO WALL




SCREWS	JD5
2	4.9
3	7.4

JOIST/TRUSS/RAFTER PERPENDICULAR TO WALL



NAILS	JD5
4	5.4
6	8.1

INTERNAL/EXTERNAL WALL JUNCTION




SCREWS	JD5
2	4.9
3	7.4

JOIST/TRUSS/RAFTER PARALLEL TO BRACING WALL


FIXING AT TOP OF BRACING WALLS TO TRUSS/RAFTER/SOLID MEMBER

NOT TO SCALE




CAPACITY PER BRACEWALL BRACKET	
JD4	JD5
3.6	3.6

POSI-STRUT SYSTEM OPTION A (REFER MANUFACTURER)




POSI-STRUT SYSTEM OPTION B (REFER MANUFACTURER)

CAPACITY PER PAIR OF ZCLIPS (kN)
JD5
3.6




I-JOIST SYSTEM (REFER MANUFACTURER)




TRUSS PERPENDICULAR TO WALL

FIXING AT TOP OF BRACING WALLS TO ENGINEERED FLOOR SYSTEMS


NOT TO SCALE




PLY-1/PLY-2/BOLT/ROD FIXING



PLY-3/AB/STRAP FIXING - I-JOIST




PLY-3/AB/STRAP FIXING - FLOOR TRUSS



BRACING AND TIE DOWN FIXING TO FLOOR SYSTEM DETAILS

NOT TO SCALE



TRUSS PARALLEL TO WALL

FIXING AT TOP OF INTERNAL WALLS TO TRUSS

NOT TO SCALE

– REPORT NAME		256865 STA JOB #	ISSUE	ISSUE DESCRIPTION	DATE
Arcadia Homes QLD CLIENT	CLIENT REFERENCE	CLIENT JOB #	0	CONSTRUCTION ISSUE	15/09/25
Lot 16 3 POWERS COURT EUMUNDI QLD 4562 ADDRESS		SP 325615 RP / SP NUMBER	1	AMENDMENT = UPDATED FLOOR PLAN	28/01/26
			–	–	–
SUNSHINE COAST REGIONAL COUNCIL LOCAL AUTHORITY			–	–	–

Smart, practical engineering solutions for residential construction
Powered by STA.

STA CONSULTING ENGINEERS

COPYRIGHT © 2021
ISO 9001:2015 Certified


SCALE NTS U.N.O.

WIND LOADING **55.30m/s**


DRG NO. S07 | DRG TOTAL -

A3 SHEET SIZE


buildable
APPROVALS
APPROVED
subject to conditions
No. 20261126
Date: 13/04/2026
Miranda Bowling A15335397
QBCC Level 3 - Accredited Certifier
0490 105 366




TYPICAL TIMBER BEAM OVER POWERTRUSS COLUMN (PTC) / NETBRACE DETAIL
NOTE TO SCALE




TYPICAL STEEL BEAM OVER POWERTRUSS COLUMN (PTC) / NETBRACE DETAIL
NOTE TO SCALE




TYPICAL POWERTRUSS BRACE (PTB) / NETBRACE DETAIL
NOTE TO SCALE




TYPICAL POWERTRUSS BRACE (PTB) / NETBRACE OVER PFC/UB/UC DETAIL
NOT TO SCALE
REFER MANUFACTURER SPEC. AND DETAILS - ENSURE TIE DOWN ANCHORS COMPLY WITH POWERTRUSS INSTALLATION DETAILS



TYPICAL POWERTRUSS COLUMN (PTC) / NETBRACE OVER TIMBER FLOOR BEAM DETAIL
NOT TO SCALE
REFER MANUFACTURER SPEC. AND DETAILS - ENSURE TIE DOWN ANCHORS COMPLY WITH POWERTRUSS INSTALLATION DETAILS



BRACING PANEL END COLUMN DETAIL
NOT TO SCALE



NOTE: HOLES SHOULD BE NEATLY CUT & CORNERS ROUNDED. HOLES LARGER THAN 150mm WILL REQUIRE RELOCATION OF BRACING PANEL - CONTACT STA CONSULTING.

PLY BRACING PENETRATIONS DETAIL
NOT TO SCALE

- REPORT NAME		256865 STA JOB #	
Arcadia Homes QLD CLIENT	CLIENT REFERENCE	CLIENT JOB #	
Lot 16 3 POWERS COURT EUMUNDI QLD 4562 ADDRESS		SP 325615 RP / SP NUMBER	
SUNSHINE COAST REGIONAL COUNCIL LOCAL AUTHORITY			

ISSUE	ISSUE DESCRIPTION	DATE
0	CONSTRUCTION ISSUE	15/09/25
1	AMENDMENT = UPDATED FLOOR PLAN	28/01/26
-	-	-
-	-	-

SCALE NTS U.N.O.

WIND LOADING **55.30m/s**

Smart, practical engineering solutions for residential construction
Powered by STA.


COPYRIGHT © 2021
ISO 9001:2015 Certified


STA CONSULTING ENGINEERS

DRG NO. S08 | DRG TOTAL -

A3 SHEET SIZE


buildable APPROVALS
APPROVED
subject to conditions
No. 20261196
Date: 13/04/2026
Miranda Dowling A15335397
QBCC Level 3 - Accredited Certifier
0490102 566






NOTE: NOTCHING DETAILS DO NOT APPLY TO GLULAM MEMBERS (PENETRATION DETAIL MAY BE USED). ADDITIONAL NOTCHING & PENETRATION DETAILS CAN BE FOUND IN AS1684 FIGURE 4.1. CONTACT STA CONSULTING SHOULD ANY NOTCHES IN TIMBER MEMBERS FALL OUTSIDE OF THESE DETAILS.

TYPICAL TIMBER MEMBER NOTCHING DETAILS
NOT TO SCALE



TYPICAL WIND BEAM INSTALLATION ELEVATION
NOT TO SCALE



TYPICAL OPENING TIE DOWN/FRAMING DETAIL
NOT TO SCALE


WALL FRAMING NOTE:
WALL FRAMING WHERE DESIGNED BY STA HAS BEEN DESIGNED FOR THE ROOF TRUSS LAYOUT AS SHOWN/ASSUMED ON LAYOUT. AN ALTERNATIVE TRUSS LAYOUT WILL REQUIRE REDESIGN AT THE BUILDERS EXPENSE AND SHOULD BE SUPPLIED TO ENGINEER FOR REVIEW.


INTERNAL NON-LOADBEARING LINTEL SCHEDULE

SPAN	MEMBER
1400	90x35 MGP10
3200	140x35 MGP10
4300	190x35 MGP10

TABLE 6.2 - FRAMING SIZES FOR NON-LOADBEARING INTERNAL WALLS

MEMBER	MINIMUM SIZE	MAXIMUM SPACING (mm)
TOP & BOTTOM PLATES	35x70	-
COMMON STUDS OF MAXIMUM HEIGHT		
<2700	70x35	600
<3600	90x35 OR 2/70x35	600
<4200	90x45 OR 2/90x35	600
STUDS SUPPORTING LINTELS	AS FOR COMMON STUDS	-





NON-LOAD BEARING EXTERNAL WALL LATERAL SUPPORT DETAILS
NOT TO SCALE

NOTE: NON-LOADBEARING EXTERNAL WALLS TO BE RESTRAINED BY; INTERSECTING WALLS, ENDS OF HANGING OR STRUTTING BEAMS, CONTINUOUS CEILING BATTENS; OR TIMBER BINDERS AT THE FOLLOWING SPACINGS TO SUIT WIND CLASSIFICATION:

N1 (34m/s) - N3 (50m/s) (NON-CYCLONIC):	3000mm	C1 (32m/s - 50m/s) (CYCLONIC)	2000mm
N4 (51m/s - 61m/s) (NON-CYCLONIC):	2000mm	C2 (51m/s - 61m/s) (CYCLONIC)	1350mm
N5 (62m/s - 74m/s) (NON-CYCLONIC):	1350mm	C3 (62m/s - 74m/s) (CYCLONIC)	900mm

- REPORT NAME		256865 STA JOB #	ISSUE	ISSUE DESCRIPTION	DATE
Arcadia Homes QLD CLIENT	CLIENT REFERENCE	CLIENT JOB #	0	CONSTRUCTION ISSUE	15/09/25
			1	AMENDMENT = UPDATED FLOOR PLAN	28/01/26
Lot 16 3 POWERS COURT EUMUNDI QLD 4562 ADDRESS		SP 325615 RP / SP NUMBER	-	-	-
SUNSHINE COAST REGIONAL COUNCIL LOCAL AUTHORITY			-	-	-

SCALE NTS U.N.O.
WIND LOADING **55.30m/s**

Smart, practical engineering solutions for residential construction
Powered by STA.

COPYRIGHT © 2021
ISO 9001:2015 Certified

STA CONSULTING ENGINEERS

DRG NO. S09 | DRG TOTAL -

A3 SHEET SIZE


buildable
APPROVED
APPROVED
subject to conditions
No. 20251196
Date: 13/04/2026
Miranda Dowling A15335397
QBCC Level 3 - Accredited Certifier
0420 102 566

BRACING FOR DIRECTION A ↑						
CODE	No	TYPE	LENGTH (m)	UNIT kN/m	VALUE (kN)	TOTAL (kN)
A1	1	PLY-1	0.8	5.6	4.48	4.48
A2	7	PLY-2	0.9	5.2	4.68	32.76
A3	1	PLY-2	1.7	5.2	8.84	8.84
A4	2	PLY-2	1.8	5.2	9.36	18.72
A5	2	PLY-2	2.4	5.2	12.48	24.96
A6	2	PTC	0.4	-	7.6	15.20
RESISTANCE REQUIRED: 98.90 kN						
RESISTANCE PROVIDED: 104.96 kN						

BRACING FOR DIRECTION B →						
CODE	No	TYPE	LENGTH (m)	UNIT kN/m	VALUE (kN)	TOTAL (kN)
B1	7	PLY-2	0.9	5.2	4.68	32.76
B2	1	PLY-2	1.2	5.2	6.24	6.24
B3	1	PLY-2	2.4	5.2	12.48	12.48
RESISTANCE REQUIRED: 45.70 kN						
RESISTANCE PROVIDED: 51.48 kN						

GENERAL NOTES:

1. REFER NOTES SHEETS IN THIS DRAWING SET PRIOR TO COMMENCEMENT OF ANY WORKS
2. A SUFFICIENT FLOOR/CEILING DIAPHRAGM TO TRANSFER BRACING LOADS IS ASSUMED UNO
3. WHERE PLY BRACING IS FIXED TO BOTH SIDES OF A WALL, THE DEPTH OF BOTTOM PLATE SHALL BE A MINIMUM OF 45mm AND TIE DOWN IS TO BE DOUBLED AT ALL LOCATIONS
4. REFER NOTES SHEETS FOR TIE DOWN DETAILS AND METHODS
5. SPECIFIC GIRDER TRUSS TIE DOWN BY TRUSS MANUFACTURER
6. CONTACT STA IF LOAD BEARING WALLS DIFFER FROM TRUSS/FLOOR DESIGN BY OTHERS



GROUND FLOOR WALL BRACING PLAN

SCALE 1:100

DIR. A
DIR. B

DRAWING KEY: (IF SHOWN ON PLAN)

- LBW: LOAD BEARING WALL UNDER -ALL EXTERNAL WALLS LBW UNO.
- LOADED STUDS
- M12 BOLT
- M12 ROD
- M16 BOLT OR 2/M12
- M16 ROD OR 2/M12
- SINGLE STRAP WITH M12 BOLT TO SLAB OR AS PER TIE DOWN DETAILS
- DOUBLE STRAP WITH M12 BOLT TO SLAB OR AS PER TIE DOWN DETAILS
- M12×100 THUNDERBOLT PRO ANCHOR + ROD

SCALE
NTS U.N.O.

WIND LOADING **55.30m/s**

- REPORT NAME	256865 STA JOB #	
Arcadia Homes QLD CLIENT	CLIENT REFERENCE	CLIENT JOB #
Lot 16 3 POWERS COURT EUMUNDI QLD 4562 ADDRESS		SP 325615 RP / SP NUMBER
SUNSHINE COAST REGIONAL COUNCIL LOCAL AUTHORITY		

ISSUE	ISSUE DESCRIPTION	DATE
0	CONSTRUCTION ISSUE	15/09/25
1	AMENDMENT = UPDATED FLOOR PLAN	28/01/26
-	-	-
-	-	-

Smart, practical engineering solutions for residential construction
Powered by STA.

COPYRIGHT © 2021
ISO 9001:2015 Certified

STA CONSULTING ENGINEERS

DRG NO. S10 | DRG TOTAL -

A3 SHEET SIZE

buildable APPROVALS
APPROVED
subject to conditions
No. 20261196
OBCC Level 3 - Accredited Certifier
0490 102 566

Form 15 Compliance certificate for building design or specification

Queensland Government

This form is the approved form that must be used in accordance with section 10 of the Building Act 1975 and sections 73 and 77 of the Building Regulation 2021 (Design-specification certificate) stating that an aspect of building work or specification will, if installed or carried out as stated in this form, comply with the building assessment provisions.

Additional explanatory information is included in the Appendix at the end of this form.

1. Property description

This section need only be completed if details of street address and property description are applicable.

E.g. in the case of (standard/generic) pool design/shell manufacture and/or patio and carport systems this section may not be applicable.

Where applicable, the description must identify all land the subject of the application.

The lot and plan details (e.g. SP/RP) are shown on title documents or a rates notice.

If the plan is not registered by title, provide previous lot and plan details.

Site Address *(include no., street, suburb/locality &postcode)*

Lot 16 3 POWERS COURT EUMUNDI QLD 4562

Lot & Plan details *(attach list if necessary)*

Lot 16 SP 325615

Local government area the land is situated in

SUNSHINE COAST REGIONAL COUNCIL

2. Description of aspect/s Certified

Clearly describe the extent of work covered by this certificate, e.g. all structural aspects of the steel roof beams.

Project Type - Single Storey Residence including:

Wall Bracing and Tie down

-
-
-
-

3. Basis of Certification

Detail the basis for giving the certificate and the extent to which tests, specifications, rules, standards, codes of practice and other publications were relied upon.

AS/NZS 1170.0:2002; AS/NZS 1170.1:2002; AS 1170.2:2021, AS 1170.4:2007, AS 4055:2021, NCC Vol. 2:2022

AS 1684.2/3:2021, AS 1720.1:2010

Wind loading: 55.30m/s

4. Reference Documentation

Clearly identify any relevant documentation, e.g. numbered structural engineering plans.

Approved Documents :

Design Documentation:

- **STA Consulting Engineers Job No. CE256865**
  DWGs No. S01 - S10 [1]

Referenced Documents:

- **Architectural drawings issued to STA on 22/01/26**

5. Building certifier reference number and building development application number

Building certifier reference number

Building development application number (if available)

6. Appointed competent person details

Under Part 6 of the Building Regulation 2021 a person must be assessed as a competent for the type of work (design-specification) by the relevant building certifier.

Name *(in full)*

Haojie (Jackie) Gong

Company Name *(if applicable)*

STA Consulting Engineers

Contact Person

Business phone number

STA Consulting Engineers

Mobile no.

Email Address

CE@staconsulting.com.au

Postal Address

Freeway Office Park, Building 3, 2728 Logan Road
Eight Mile Plains **State QLD** **Postcode 4113**

License or registration type *(if applicable)*

RPEQ

License or registration number *(if applicable)*

Haojie (Jackie) Gong, MIEAust, NER 5759729, RPEQ 20027

7. Signature of competent person

This certificate must be signed by the individual assessed and appointed by the building certifier as competent to give design-specification help.

Signature

Date

28 January 2026

LOCAL GOVERNMENT USE ONLY

Date Received		Reference Number/s	